



KEY

- Prefix items
- d - demolish item noted
- n - new item (noted for clarity where ambiguous)
- s - salvage item noted and issue to principal for storage
- sr - salvage and reinstate item noted in new position
- ex - existing item (noted for clarity where ambiguous)
- italic text refer to finishes schedule for details

AP1 Acoustic panel 3, Autex Cube 12mm colour "Empire", mechanical or adhesive fix refer details, where adhesive fix as per manufacturers instructions

AP2 Acoustic panel 2, Autex Cube 24mm colour "Empire", mechanical or adhesive fix refer details, where adhesive fix as per manufacturers instructions

as adjustable shelf at 50mm centres vertically

avc AV computer, supply and mount by Builder, Commission by UQ ITS, refer AV section in Specification

avl AV lcd screen, supply and mount by Builder, Commission by UQ ITS, refer AV section in Specification

avr AV rack, supply and mount by Builder, Commission by UQ ITS, refer AV section in Specification

bin bin, wheeie bin by UQ

ctg ceiling 600x600 suspended grid and tile refer finishes schedule

ch# ceiling height above floor level

cos check dimensions on site

cpt# carpet (type # where new), refer finishes schedule

csp ceiling set plasterboard pain PT3

cde existing terrazzo floor tiles 400x400, refer PC sum for cleaning

ctf existing terracotta floor tiles 150x150, refer PC sum for cleaning

ctt ceiling, timber batten lift and shift tile

cws ceiling exposed waffle slab, patch and make good where affected by demolition, Paint all waffle and plastic inert strips in room 208 209 PT3

Da Door Auto Opening slider, Dorma EL301 operator, refer door schedule

DF1 drink fountainZip CHILL FOUNTAIN ADULT CFB140FA, installed in location of former drink fountain (refers future level 3 works only)

ebg electrical break glass escape button, refer electrical

ecp electrical cables in partition, refer electrical

ect electrical comms tray, refer electrical

edr electrical communications data rack, refer electrical

eds electrical ducted skirting (Black), refer electrical

efb electrical floor box, refer electrical

efd electrical floor duct existing retained, location to be confirmed by builder

elf electrical light fitting, refer electrical

em entry matting

eml electrical magnetic lock, refer electrical

epb electrical push button door opener

epc electrical proximity card reader, refer electrical

ept electrical power tray, refer electrical

esb switchboard, refer electrical

ess electrical soft wiring starter socket, refer electrical

F.# Furniture Type #, supply by UQ, refer furniture schedule

ht fire hose reel (existing)

hsk sink and associated plumbing

hyd fire hydrant (existing)

ip infill panel, measure and scribe on site

J.# Joinery Number (Jx when existing), refer details

jps joinery pen shelf 90x42 tasmanian oak solid shelf, 30% satin clear finish

ik satin chrome flush lock, 0017 Hafele barrels keyed alike

mar mechanical air register refer mechanical documents

mdw mechanical duct work, also refer mechanical

mg make good surface where affected by demolition

mtp mechanical refrigerant pipes, refer mechanical

pb plasterboard, set plaster joints

Ph Partition Existing lightweight

Pr# Partition New # type refer partition schedule

pse plaster set edge, tear off bead or setting angle.

PT# paint colour #, refer finishes schedule

QS Acoustic panel 1, 450x450x50mm Autex Quietpace, Nude White, adhesive fix to ceiling slabs as per manufacturers instructions + 1 mechanical fixing per panel

RB# Roller blind, refer finishes schedule

sgu signage supplied and installed by UQ

sgw sliding glass whiteboard, refer details

skv vinyl skirting black, 3000mm FLAT, (NOT feather edge)

tb# timber batten modules 1800h x 400centres, refer elevations and details

wb Vitreous Enamel Steel whiteboard, Just Boards LX800 slim 4mm white powdercoated frame, check custom dimension on site

WS.# workstation number, By Builders workstation contractor, refer details

wsc workstation cable tray CMS 50x50 basket on 100mm bracket

wsp workstation power module CMS Centra CERCO2U - 2 x Rotating GPO w/ 2 X USB (1 x Type B, 1 x Type C)

FINISHES SCHEDULE

AP1 Acoustic panel 3, Autex Cube 12mm colour "Empire", mechanical or adhesive fix refer details, where adhesive fix as per manufacturers instructions

AP2 Acoustic panel 2, Autex Cube 24mm colour "Empire", mechanical or adhesive fix refer details, where adhesive fix as per manufacturers instructions

cpt 1 Carpet Tiles Ontera Nordic Stories Tectonic Colour Crea TCT120-178 500x500 carpet tiles, laid monolithic

cpt 2 Carpet Tiles Ontera Nordic Stories Hidden Plains Colour Aluvium HDP133-59 500x500 carpet tiles, laid monolithic

cte Ceiling tile eggcrate, white Eggcrate louvre grille Tiles in 600 x 600 grid (return air path)

ctg Ceiling tile and grid, Armstrong White Dune Angled Tegular Tiles in 600 x 600 grid

ctj ceiling grid and tile timber batten lift and shift supplied from Supawood

L1 LAMINEX 200 WHITE natural finish with matching PVC tough edge

L2 LAMINEX 461 CHARCOAL natural finish with matching PVC tough edge

ln1 Lino 2 5mm Intermoleum Lino "3139 Lava" set flush with perimeter timber

PT1 Dulux Wash and Wear Low Sheen, tinted to White Duck Quarter Strength PN1A2

PT2 Dulux Wash&Wear Low Sheen tinted to SG6G8 Domino, Top protective coat of Intergrain Ultraclear satin

PT3 Ceiling White FLAT Acrylic

PT4 Resene Blast Grey base no colour sparkles (to match existing on doors)

PT5 Dulux Wash and Wear Low Sheen tinted to Dulux Buff II S11B1 (matches existing)

QS Acoustic panel 1, 450x450x50mm Autex Quietpace, Nude White, adhesive fix to ceiling slab as per manufacturers instructions + 1 mechanical fixing

RB1 Chain Drive Roller Blind, Vertulux 1.02 ezydrive roller system with chain at ends shown RB1 on plan, Fabric Euroscreen Colour Blanc, 1250 drop, White powdercoat base rail

RB2 Motorised Roller Blind wall series on Somfy Controller, Vertulux, Fabric Euroscreen Colour Gummetal, 1250 drop, Black powdercoat base rail

skv vinyl skirting black, 3000mm FLAT, (NOT feather edge)

T1 Tasmanian Oak Batten dressed to 32x64, 30% satin clear polyurethane finish

T2 Tasmanian Oak Batten dressed to 32x32, 30% satin clear polyurethane finish

T3 TV1 veneer, 32mm board, solid timber edge, 30% satin clear polyurethane finish

T4 Tasmanian Oak Solids, 30% clear satin polyurethane finish

TV1 Tasmanian Oak Veneer, QUARTER CUT, 30% satin polyurethane clear finish